	P/C4-19-22 SERVICE
SP	CA 4-21-22
	1stR
	2nd R
	3rd R
	B/C

CITY OF BROOK PARK, OHIO

ORDINANCE NO: 11255-2022

INTRODUCED BY: MAYOR ORCUTT

AN ORDINANCE

AUTHORIZING THE MAYOR TO ENTER INTO A CONTRACT WITH HENDERSON PRODUCTS (SOURCEWELL CONTRACT #080818-HPI/ SOURCEWELL #: 39065)
FOR THE PURCHASE OF A 2022 SINGLE AXLE SNOW AND ICE CONTROL TRUCK EQUIPMENT PACKAGE, AND DECLARING AN EMERGENCY

NOW THEREFORE, BE IT ORDAINED, by the Council of the City of Brook Park, State of Ohio, that:

SECTION 1: The Mayor is hereby authorized to enter into a Sourcewell contract #080818-HPI/Sourcewell #: 39065 with Henderson Products, Inc., for the purchase of a 2022 Single Axle Snow and Ice Control Truck Equipment Package, a copy of said contract is attached hereto and incorporated herein as Exhibit "A".

SECTION 2: The money needed for the aforesaid transaction shall be paid from 401-432 Capital Funds, and shall not exceed \$95,836.00.

SECTION 3: It is found and determined that all formal actions of this Council concerning and relating to the adoption of this Ordinance were adopted in an open meeting of this Council, and that all deliberations of this Council and of any of its committees that resulted in such formal action were in meetings open to the public in compliance with all legal requirements, including Section 121.22 of the Ohio Revised Code.

ECTION 4: This Ordinance is hereby declared to be an emergency measure immediately necessary for the preservation of the public peace, health, safety and welfare of said City, and for the further reason to provide for usual and ordinary operation of the City's Service Department; therefore this Ordinance shall take effect and be in force immediately from and after its passage and approval by the Mayor.

RECEIVED

APR 1 9 2022

BROOK PARK CITY COUNCIL

PASSED: April 26, 2022	PRESIDENT OF COUNCIL
ATTEST: ON Johnson Clerk of Council	APPROVED: MAYOR
	4-26-22 DATE
CERTIFICATE Carol Johnson, Clerk of Council, of the City of Brook Park, Ohio, do hereby certify that the foregoing is a true and accurate copy of Ordinance Resolution No. 11255 - 2022 passed on the 20 day of April 20 22 by said council. Clerk of Council	I, Carol Johnson, Clerk of Council for the City of Brook Park, State of Chio, do hereby certify that there is no newspaper of general circulation in the municipality and that publication of the foregoing ordinance resolutions was made by posting true copies at five of the most publiplaces in said municipality as determined by Ordinance No. 4838-197 location. City Hall 6161 Engle Road, Police Station 17401 Holland Roa #2 Fire Station 22530 Ruple Parkway, #3 Fire Station 17401 Holland Roa Brook Park Library 6165 Engle Road, for a period of fifteen days. CAROLIOHNSON Clerk of Council
Troyer Nay Mencini	

I HERIBY APPHOVE THE WITHIN INSTRUMENT AS TO LEGAL FORM AND CORRECTNESS

Roberts - Scott - Coyne - Poindexter - Salvatore - -

DIRECTOR OF LAW

Boardof Cortael 4.18.22 PRICE QUOTE BY: PHONE NO PRICE EA. DEPT. TAUOIMA DESCRIPTION Dump Body, Dnow Plow Hetch; lentral Hydraulic septem and falt spreades installed on our 2022 Western Star Truck Massis see attached Quot

Noto Dourcewell Continue 18. HFI

Have Law + Emance Hart

Legislation + Purchasing

Legislation + ASAP Due to Durchan



HENDERSON CUSTOMER QUOTE

PRODUCTS, INC.

Quote #161028 Rev #28

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

Quoted By: Ross Repp

Phone: 419-617-7509

Email: rrepp@hendersonproducts.com

Cell: 4195696166

Fax:

To: CITY OF BROOK PARK, OH

Attn: JOHN PENSIS Quote Date: 4/12/2022 Valid Until: 5/12/2022

Sourcewell Contract# 080818-HPI

Sourcewell #: 39065

2022 SINGLE AXLE SNOW & ICE CONTROL TRUCK EQUIPMENT PACKAGE

Henderson Products is pleased to present the following quote. Please contact us if you have any questions.

Snow Plow Hitch Reversing Cylinder Style: None or Top mount reversing cylinders

Plow Portion Hitch: Plow portion not included, existing plow

Hitch, Truck Portion: Pin & loop hitch, Hercules

Bumper to Frame Mounting Kit: No, upfitter supplied mounting Hydraulic Lift Cylinder: 4" x 2" x 10" Double Acting Nitrided Lift Cylinder

High Pressure QD System: No High Pressure QD System Holding Valve for Lift Cylinder: No Holding Valve For Lift Cylinder

Custom Options: Note Custom Details Below

Option 1 Description: HERCULES PIN & LOOP PLOW HITCH

Option 2 Description: STRUCTURAL STEEL CONSTRUCTION

Option 3 Description: LIFT BEAM FOLDS FLAT WHEN NOT IN USE

HPI MarkE

COUNTRY/LANGUAGE: USA/ENGLISH

FAMILY: MARK E, CLASSIC

FLOOR LENGTH: 11' FLOOR LENGTH

SIDE HEIGHT: 36" SIDE HEIGHT

BODY MATERIAL (SIDES/HEADSHEET): 7GA 201SS SIDES/HEADSHEET

SIDE BRACES: (2) V CRIMP SIDE BRACES

TOP RAIL/RUB RAIL MATERIAL: 7GA 201SS TOP & RUB RAILS

REAR BOLSTER HEIGHT: 8" BOLSTER, 2-1/8" POCKETS

REAR BOLSTER MATERIAL: 7GA 201SS REAR BOLSTERS

FRONT BOLSTER: NO FRONT BOLSTERS

FLOOR MATERIAL: 1/4" AR400 FLOOR

HOIST TYPE: TRN MT HOIST, INT DH, SUBFRM, DA

CYLINDER MODEL: CS/G4, DBL ACT, 2YR SALT WTY*

HOIST MOUNT TYPE: STANDARD SUBFRAME

INSTALL HOIST & CRADLE: UPFITTER INSTALLED H&C

LONGSILLS: 5" I-BEAM LONGSILLS, FULL WELD

BODY HINGE MAINTENANCE: GREASEABLE PINS, NO BUSHINGS

TAILGATE STYLE: CONFIGURABLE STANDARD TAILGATE

TAILGATE SHEET MATERIAL: 7GA 201SS TAILGATE SHEET

TAILGATE LINER: NO TAILGATE LINER









HENDERSON CUSTOMER QUOTE

PRODUCTS, INC.

Page 2 Quote #161028 Rev #28

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

COAL CHUTE: NO COAL CHUTE

TAILGATE BRACE: 2 HORIZONTAL TAILGATE BRACE

TAILGATE LIFT STYLE/LOCATION: FORMED LIFT LOOP, TOP BRACE

TAILGATE RELEASE & CONTROL: DOUBLE ACTING, SS BUSHING, TG RELEASE

TAILGATE HINGE: STD, 1-1/4" PIN, 1" PLT

TAILGATE CHAINS: ZINC TAILGATE CHAINS

HORIZONTAL J-HOOKS: NO HORIZONTAL J-HOOKS

TAILGATE PIN LANYARDS: NO TAILGATE PIN LANYARDS

TAILGATE AIR VALVE: UPFITTER SUPPLIED TAILGATE AIR VALVE

LUBRICATION: GREASEABLE PINS, JAWS, & SHAFT

CABSHIELD STYLE/WIDTH/OVERHANG: WELD-ON, 22"x86", NO TARP SHROUD

CABSHIELD MATERIAL: 201SS, 10GA PANEL, 7GA ENDS

CABSHIELD INSTALLATION: CABSHIELD SHIPS LOOSE

CABSHIELD OFFSET: OFFSET NOT APPLICABLE

CABSHIELD LIGHTING: CS LIGHTS, 2 FORWARD, 1 EACH SIDE

ASPHALT LIP: NO ASPHALT LIP

SIDE BOARDS: UPFITTER SUPPLIED SIDEBOARDS

SIDE LADDER LOCATION: LADDER/GRBHND, DS FRNT, INSTL

SIDE LADDER TYPE: LADDER, PULLOUT 201SS, FIXED UPR

INTERIOR STEPS: NO INTERIOR STEPS

RUB RAIL LIGHTING: NO RUB RAIL LIGHTING

REAR BOLSTER MARKER LIGHTING: 2.5" RED REAR BLSTR LIGHT

REAR FACING REAR BOLSTER LIGHT: 3 OBROUND LIGHT

LIGHTING ADD ONS: NO BOLT-ON LIGHT BOX

LIGHTING PACKAGE: UPFITTER SUPPLIED LIGHT PACK

PWS TANKS: NO PREWET TANKS

PREWET PREP: NO PREWET BOX BRACKET

WALK RAILS: NO WALK RAILS TARP RAILS: NO TARP RAILS

VIBRATOR LOCATION: NO VIBRATOR

TGS INSTALLATION: NO FACTORY INSTALLED TGS

TGS INTEGRATION: NO TGS SPILL SHIELDS

TGS/ASPHALT LIP MOUNT HOLES: NO MOUNT HOLES IN BOLSTER

FINISH PREP: WASH & PRIME MILD PARTS ONLY

PAINT/FINISH: NO FINISH

NOTE 1:: NO ADDITIONAL CUSTOM OPTIONS

NOTE 2:: NO ADDITIONAL CUSTOM OPTIONS

NOTE 3:: NO ADDITIONAL CUSTOM OPTIONS NOTE 4: NO ADDITIONAL CUSTOM OPTIONS

NOTE 5: NO ADDITIONAL CUSTOM OPTIONS

NOTE 6: NO ADDITIONAL CUSTOM OPTIONS

NOTE 7: NO ADDITIONAL CUSTOM OPTIONS

NOTE 8: NO ADDITIONAL CUSTOM OPTIONS

FSH salt / sand spreader

Spreader Model: FSH-II Salt/Sand Spreader

Hopper length: 11'









HENDERSON CUSTOMER QUOTE

PRODUCTS, INC.

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

Quote #161028 Rev #28

Hopper material: 201SS - 10 GA sides/ends, 7 GA sills/floor Capacity: FSH-II 56" (7.6 CY) w/ formed chain shields standard

Conveyor: Dual 7" dia. augers

Gearcase: 3.6:1 planetary gearcase

Flow Divider: Yes, Factory Installed (recommended)

Chute type: Standard Dump Over Chute Same Material as Hopper

Tilt-up spinner: Tilt-up spinner with hand wrench, SS (loose "SL")

Spinner disk: 20" urethane spinner disk

Inverted vee: Inverted vee, 201ss

Install inverted vee: Install at factory

Screen type: Std. top grate screens

Install top grate screens: Install at factory

Hold down kits: Dump body kit w/ rachet straps

Extended front idler grease tubes: Extended front idler grease tubes

Trunnion latch for tailgate: Trunnion latch, Mild Channel (loose "SL")

Option 1 Description: SS TRUNNION ILO MILD

Installation Workup

Chassis Delivery To Henderson: Henderson Picks Up (100 miles or less) Completed Truck Delivery Method: Henderson Delivers (100 miles or less)

Chassis Make: Westernstar

Chassis Model Yr: 2023 Chassis Model: 4700

Useable CA/CT: 96 Inch Front Frame Ext?: Yes Frnt Frame Ext Type: Full Front Frame Wall: Single Wall

Front Frame Width: 42"

Pump Location: Transmission Mount Pump

Transmission Type: Automatic

Transmission Model: Allison Transmission

Hitch Type: Hercules Hitch

Mount Type: Engineered Truck Hitch (sales to order hitch w/ unit)

Mount Spec: (1)178128 KIT, HITCH, HERCULES, EXT, FRAME, 9

Front Bumper: OEM Bumper Cut and Split Hitch Options 1: (1)177873 PLATE, GUSSET,

Dump Body Type: Mark E Single Axle

Floor Length: (11') floor length Hoist Type: Tele Trun HoIst with Subframe, Internal Doghouse

Cylinder Type: Double Acting Body Material (Sides/ends): Stainless Steel Type Body Material

Tailgate Release Type: IDC Supplied manual air over air valve Pressure Protection Valve: Direct to air tank valve (All except Int, Mack &

Volvo)









HENDERSON

CUSTOMER QUOTE

Page 4 Quote #161028 Rev #28

PRODUCTS, INC.

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

Cabshield Install: Supl'd by fact, welded to body @ IDC, sales to order w/ unit Grab Handle(s): (1) Factory supl'd, install @ IDC (Sales to order with unit) Ladder(s): Supplied by factory, Install @ IDC (sales to order w/ unit) Ladder Install QTY (Dump): (1) LADDER INSTALLED @ IDC (LABOR ONLY) Ladder Install Style (Dump) 1: 3 Step Pull Out

Ladder Install Loc 1 (Dump): Driver Side Front

Body Install Options 1: (4)114775.201 BRACKET, HOLD DOWN, DUMP

Body Spec Notes:

Spreader Type: FSH

FSH Drive Type: Hydraulic FSH Mount Type: Slip in Mount

Slip in Tie Downs: Factory Hold down kit (Sales to order with unit)

Trunnion Latch: Install Fact Sup'ld Trun Latch Bar, sales to order with unit

FSH Spinner Configuration: Standard Spinner install

HYD QD Mount Brackets: Stainless Steel QD Mount in front of dump body bolster

Chassis Accessories: Yes (SELECT RELATED OPTIONS BELOW)

Mudflaps (Rear): Swinging w/Logo

Mudflap Type (Rear): 36" Swinging, SS (with LOGO)

Mudflaps (Front): Body Mounted w/Logo

Mudflap Type (Front): Body Mounted Rubber, SS, w/ anti-sail brackets W/ LOGO

Pintle Plate: Yes (select from options below)

Pintle Plate Configuration: 3/4" Plate, PH20 Holes, SA w/ SubFrm (3LTC)

Pintle Plate D-Rings: Qty (2) 1" D-rings, 50 deg bend

Pintle Hook: Not Required

Trailer Plug (1): 7 Pin Trailer Plug, Truck end 7-Way RV, new style (municipal)

Truck Wash: Complete Truck Wash/Clean/Vac 1

Warranty: Standard 1 Year Warranty Inspection: Walk-around meeting only

Reflective Tape: Reflective Tape, Henderson Logo (60' Linear)

Install Touch-up: Basic Installation Touch-Up

Electrical: Yes (SELECT RELATED OPTIONS BELOW) Power Distribution Panel: Power Distribution Panel Misc Electrical Supplies: Req'd Misc Elect Supplies Plow Lights: Plow Lts, LED, Heated, Tlite, Round, Pair

Plow Light Brackets: Plow Lt Brckts, SS, FRTLNR/Western Star/Other, Pair

Worklight(s) QTY: (QTY 1) Work Light (Select type below) Worklight (1) Type: LED, Worklight, 4in Round (Optilux)

Worklight (1) Gen Location: On rear of body

Cabshield Warning Light Qty: Qty 6 Lights (Order Holes with Unit)

Cabshield Warning Lights: QTY 3 6" LED Ovl Strobe Green/Qty 3 LED Ovl Strobe

Cabshield Lighting Harness: Cabshield Warning Lights Only (qty 2-6)

Rear Dump Bolster (S/T/T): LED S/T/T, kit (OH) (order holes)

OEM Light Remount: Remount OEM Chassis Lights









HENDERSON

PRODUCTS, INC.

CUSTOMER QUOTE

Page 5

Quote #161028

Rev #28

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

Rear Dump Bolster (Back-up): B/U Lights, LED, Clear, Oval, pair (Order holes with body)

Rear Dump Bolster Strobes: 6" LED Oval Strobes, 1 Amber, 1 Green (order holes w/unit)

Rear Dump Bolster Light Boxes: Single Oval, 6" SS Lightboxes, Pair, Externally Mounted

Back up alarm: Backup Alarm, 97db

Body up switch/light: Supplied with Hydraulics, IDC install Brake controller: Brake Controller, Voyager Brake Controller

Backbone & Wire Standoffs: 10' Backbone (For SA)

Electrical Spec Notes:

Hydraulics: Full Hydraulic Package

Hyd Supplier: Certified (Select Pkg Below)
Hyd Supplier (Spec): Certified Power B Package

Controls Type: Air Controls

PTO Type: Included in Hydraulics Package Reservoir Type: Supplied With Hydraulics

Reservoir Spec:

Valve Enclosure Type: Supplied With Hydraulics Low Oil Indicator: Yes, included in Hyd Pkg Return Filter: Provided with Hydraulics SS Tubing Upgrade: SA,F&R lines,6'Frnt,9'Rr Quick Coupler Upgrade: Standard Quick Couplers

Hyd Options 1: (1)162781 KIT, RAM MOUNT

Hydraulics Notes:

*SS QUICK COUPLERS IN HYD KIT

*SS VALVE ENCLOSURE/OIL RESERVOIR COMBO TANK

*AIR LEVER PEDISTAL W/ FREEDOM 2 ELECTRIC SPREADER CONTROLLER

*PLOW BALANCE VALVE & COUPLER PREASURE RELEASE VALVE

Disclaimer: Paint not guaranteed to match OEM chassis color

IDC Paint Location: IDC-OH

Undercoat: Undercoat (Body Underside & Chassis)

Paint Code & Color (from color charts):









HENDERSON

PRODUCTS, INC.

2177 STATE ROUTE 19 BUCYRUS, OH 44820 PHONE: 419-617-7509 FAX: 563-927-7106

CUSTOMER QUOTE

Page 6 Quote #161028 Rev #28

Total configured price: \$105,485.00

Sourcewell package discount: 10% plus freight Discounted single package price: \$95,836.00

Package(s): 1 Total: \$95,836.00

Due to the volatility in material costs and chassis delays, pricing is subject to change at time of manufacturing and/or upfit.

Due to current raw material market conditions this quote includes a surcharge on Henderson equipment. Quotes exceeding the expressed quote validity date are subject to surcharge revisions.

Signed:	Da	ate: _		

Quote notes:

Option
Remove Freedom Controller and use Dual Knob Spreader Controls, Deduct \$1,175.00

Remove Full Loadsense Plow Balance, Deduct \$1,844.00





